



Fairfield County Engineer

3026 W. Fair Ave.
Lancaster, OH 43130
Main: (740) 652-2300
Fax: (740) 687-7055

FAI-CR55-3.319 HOC-21 HAMBURG ROAD BRIDGE REPLACEMENT PROJECT ADDENDUM #1

February 25, 2026

The following information supplements and amends the original Bid Documents and Specifications and shall become part of the Contract Documents.

1. Replace sheet 6 of the plans with the attached. Item 505 Pile Driving Equipment Mobilization has been removed.
2. Replace sheet 38 of the plans with the attached. Item 505 Pile Driving Equipment Mobilization has been removed.
3. Replace pages 7.2, 7.3 and 7.4 with the attached 7.2-ADDENDUM #1, 7.3-ADDENDUM #1, and 7.4-ADDENDUM #1. Item 505 Pile Driving Equipment Mobilization has been removed.

A handwritten signature in blue ink, appearing to read "Bill Maravy".

Bill Maravy, P.E.
Deputy Engineer

Jeremiah D. Upp, P.E., P.S., County Engineer

**FAIRFIELD COUNTY ENGINEER'S OFFICE
FAI-CR55-3.319 HOC-21 HAMBURG ROAD
BRIDGE REPLACEMENT PROJECT**

REF. NO.	ITEM NO.	ESTIMATED QUANTITY (A)	UNIT	DESCRIPTION	UNIT PRICE TOTAL (D)	TOTAL COST (AXD)=(E) (E)
1	201	1	LUMP	CLEARING & GRUBBING		
2	202	2625	SY	PAVEMENT REMOVED		
3	202	80	FT	PIPE REMOVED, 24" DIAMETER & UNDER		
4	202	700	FT	GUARDRAIL REMOVED		
5	202	3	EA	ANCHOR ASSEMBLY REMOVED, TYPE A		
6	202	2	EA	ANCHOR ASSEMBLY REMOVED, TYPE T		
7	202	317	FT	FENCE REMOVED		
8	203	5616	CY	EXCAVATION		
9	203	1564	CY	EMBANKMENT		
10	204	3104	SY	SUBGRADE COMPACTION		
11	204	100	CY	EXCAVATION OF SUBGRADE		
12	204	100	CY	GRANULAR MATERIAL, TYPE F		
13	204	8	HOUR	PROOF ROLLING		
14	204	200	SY	GEOTEXTILE FABRIC		
15	606	525	FT	GUARDRAIL, TYPE MGS		
16	606	3	EA	ANCHOR ASSEMBLY, MGS TYPE A		
17	606	5	EA	ANCHOR ASSEMBLY, MGS TYPE T		
18	606	4	EA	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1		
19	659	2	EA	SOIL ANALYSIS TEST		
20	659	702	CY	TOPSOIL		
21	659	6324	SY	SEEDING & MULCHING		
22	659	316	SY	REPAIR SEEDING & MULCHING		
23	659	0.88	TON	COMMERCIAL FERTILIZER		
24	659	1.31	ACRE	LIME		
25	659	36	MGAL	WATER		
26	670	287	SY	DITCH EROSION PROTECTION MAT, TYPE B		
27	832	1	LUMP	STORM WATER POLLUTION PREVENTION PLAN		
28	832	26000	EA	EROSION CONTROL		
29	836	187	SY	SEEDING & EROSION CONTROL W/TURF REINFORCING MAT, TYPE 1		
30	836	33	SY	SEEDING & EROSION CONTROL W/TURF REINFORCING MAT, TYPE 3		
31	511	0.66	CY	CLASS QC1 CONCRETE, HEADWALL		
32	601	5	CY	ROCK CHANNEL PROTECTION, TYPE C W/GEOTEXTILE FABRIC		

**FAIRFIELD COUNTY ENGINEER'S OFFICE
FAI-CR55-3.319 HOC-21 HAMBURG ROAD
BRIDGE REPLACEMENT PROJECT**

REF. NO.	ITEM NO.	ESTIMATED QUANTITY (A)	UNIT	DESCRIPTION	UNIT PRICE TOTAL (D)	TOTAL COST (AXD)=(E) (E)
33	605	189	FT	AGGREGATE DRAINS		
34	611	20	FT	6" CONDUIT, TYPE B		
35	611	20	FT	6" CONDUIT, TYPE E		
36	611	20	FT	6" CONDUIT, TYPE F		
37	611	89	FT	12" CONDUIT, TYPE D		
38	611	130	FT	18" CONDUIT, TYPE B		
39	611	1	EA	CATCH BASIN, NO. 2-2A		
40	254	365	SY	PAVEMENT PLANING, ASPHALT CONCRETE		
41	301	428	CY	ASPHALT CONCRETE BASE, PG64-22 (449)		
42	304	575	CY	AGGREGATE BASE		
43	407	284	GAL	NON-TRACKING TACK COAT		
44	411	41	CY	STABILIZED CRUSHED AGGREGATE		
45	441	117	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (449), PG64-22		
46	441	122	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2 (449)		
47	642	0.45	MILE	EDGE LINE, 4", TYPE 1		
48	642	0.23	MILE	CENTER LINE, TYPE 1		
49	202	1	LUMP	STRUCTURE REMOVED, OVER 20 FOOT SPAN		
50	202	122	SY	WEARING COURSE REMOVED		
51	203	628	CY	GRANULAR MATERIAL, TYPE B, AS PER PLAN		
52	204	237	SY	GEOGRID		
53	503	1	LUMP	COFFERDAMS & EXCAVATION BRACING		
54	503	178	CY	UNCLASSIFIED EXCAVATION		
55	507	630	FT	STEEL PILES HP10X42, FURNISHED		
56	507	570	FT	PREBORED HOLES		
57	509	26517	LB	EPOXY COATED STEEL REINFORCEMENT		
58	511	87	CY	CLASS QC2 CONCRETE, BRIDGE DECK		
59	511	68	CY	CLASS QC1 CONCRETE, ABUTMENT INCLUDING FOOTING		
60	512	91	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)		
61	513	82900	LB	STRUCTURAL STEEL MEMBERS, LEVEL 1, AS PER PLAN (W30 X 124, 71'-0" LENGTH)		
62	513	1260	EA	WELDED STUD SHEAR CONNECTORS		
63	516	52	SF	1/2" PREFORMED EXPANSION JOINT FILLER		
64	516	54	SF	1" PREFORMED EXPANSION JOINT FILLER		

**FAIRFIELD COUNTY ENGINEER'S OFFICE
FAI-CR55-3.319 HOC-21 HAMBURG ROAD
BRIDGE REPLACEMENT PROJECT**

REF. NO.	ITEM NO.	ESTIMATED QUANTITY (A)	UNIT	DESCRIPTION	UNIT PRICE TOTAL (D)	TOTAL COST (AXD)=(E) (E)
65	516	42	SF	2" PREFORMED EXPANSION JOINT FILLER		
66	516	85	FT	INTEGRAL ABUTMENT EXPANSION JOINT SEAL		
67	516	10	EA	ELASTOMERIC BEARING W/INTERNAL LAMINATES & LOAD PLATE (NEOPRENE), AS PER PLAN (LOAD PLATE 11.5" X 14" X 1.50", NEOPRENE 10.5" X 13" X 1.69")		
68	517	150	FT	RAILING (TWIN STEEL TUBE)		
69	518	58	CY	POROUS BACKFILL W/GEOTEXTILE FABRIC		
70	SPECIAL	167	FT	STEEL DRIP STRIP		
71	518	96	FT	6" PERFORATED CORRUGATED PLASTIC PIPE		
72	518	54	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS		
73	526	124	SY	REINFORCED CONCRETE APPROACH SLABS (T=13")		
74	526	56	FT	TYPE A INSTALLATION		
75	601	193	CY	ROCK CHANNEL PROTECTION, TYPE C W/GEOTEXTILE FABRIC		
76	625	1	EA	STRUCTURE GROUNDING SYSTEM		
77	614	1	LUMP	MAINTAINING TRAFFIC		
78	623	1	LUMP	CONSTRUCTION LAYOUT STAKES & SURVEYING		
79	624	1	LUMP	MOBILIZATION		

TOTAL AMOUNT OF BID: \$ _____

Company Name: _____

(Signature): _____

Address: _____

(Printed): _____

Title: _____

Phone: _____


E-Mail: _____

Fax: _____

Date: _____

SHEET NUMBER								PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
7	38							ITEM	EXT	TOTAL				
													TRAFFIC CONTROL	
0.45								642	00100	0.45	MILE		EDGE LINE, 4", TYPE 1	
0.23								642	00300	0.23	MILE		CENTER LINE, TYPE 1	
													STRUCTURE OVER 20 FOOT SPAN (SFN 2337258)	
								202	11002	LS			STRUCTURE REMOVED, OVER 20 FOOT SPAN	
122								202	23500	122	SY		WEARING COURSE REMOVED	
								203	35111	628	CY		GRANULAR MATERIAL, TYPE B, AS PER PLAN	36
628								204	51000	237	SY		GEOGRID	
237								503	11100	LS			COFFERDAMS AND EXCAVATION BRACING	
								503	21100	178	CY		UNCLASSIFIED EXCAVATION	
178								505	11100	LS			PILE DRIVING EQUIPMENT MOBILIZATION	
								507	00100	630	FT		STEEL PILLS HP10X42, FURNISHED	
630								507	92200	570	FT		PREBORED HOLES	
570								509	10000	26,517	LB		EPOXY COATED STEEL REINFORCEMENT	
26,517								511	34444	87	CY		CLASS QC2 CONCRETE, BRIDGE DECK	
87								511	43510	68	CY		CLASS QC1 CONCRETE, ABUTMENT INCLUDING FOOTING	
68								512	10100	91	SY		SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
91								513	10221	82,900	LB		STRUCTURAL STEEL MEMBERS, LEVEL 1, AS PER PLAN(W30x124, 71'-0" length)	36
82,900								513	20000	1,260	EACH		WELDED STUD SHEAR CONNECTORS	
1,260								516	13200	52	SF		1/2" PREFORMED EXPANSION JOINT FILLER	
52								516	13600	54	SF		1" PREFORMED EXPANSION JOINT FILLER	
54								516	13900	42	SF		2" PREFORMED EXPANSION JOINT FILLER	
42								516	14014	85	FT		INTEGRAL ABUTMENT EXPANSION JOINT SEAL	
85								516	44001	10	EACH		ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), AS PER PLAN(Load Plate 11.5"x14"x1.50", Neoprene 10.5"x13"x1.69")	42
10								517	70000	150	FT		RAILING (TWIN STEEL TUBE)	
150								518	21200	58	CY		POROUS BACKFILL WITH GEOTEXTILE FABRIC	
58								SPECIAL	51822300	167	FT		STEEL DRIP STRIP	
167								518	40000	96	FT		6" PERFORATED CORRUGATED PLASTIC PIPE	
96								518	40010	54	FT		6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	
54								526	15000	124	SY		REINFORCED CONCRETE APPROACH SLABS (T=13")	
124								526	90010	56	FT		TYPE A INSTALLATION	
56								601	32204	193	CY		ROCK CHANNEL PROTECTION, TYPE C WITH GEOTEXTILE FABRIC	
193								625	33000	1	EACH		STRUCTURE GROUNDING SYSTEM	
1								614	11000	LS			INCIDENTALS	
								623	10000	LS			CONSTRUCTION LAYOUT STAKES AND SURVEYING	
								624	10000	LS			MOBILIZATION	
													MAINTAINING TRAFFIC	

Remove Pay Item 505
 Pile Driving Equipment
 Mobilization.



GENERAL SUMMARY

DESIGN AGENCY
SDLZ

DESIGNER:
 SDB

REVIEWER:
 CAM 03/13/25

PROJECT ID:
 113793

SHEET TOTAL
 P.6 | 49

FUNDING	ESTIMATED QUANTITIES					REAR	FORWARD	SUPER-	GENERAL	REF. SHEET
	ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENT	ABUTMENT	STRUCTURE	NUMBER	
	202	11002	LS		STRUCTURE REMOVED, OVER 20 FOOT SPAN				LS	
	202	23500	122	SY	WEARING COURSE REMOVED			122		
	203	35111	628	CY	GRANULAR MATERIAL, TYPE B, AS PER PLAN	303	325			
	204	51000	237	SY	GEOGRID	114	123			
	503	11100	LS		COFFERDAMS AND EXCAVATION BRACING				LS	
	503	11100	178	CY	UNCLASSIFIED EXCAVATION	85	93			
	505	11100	LS		PILE DRIVING EQUIPMENT MOBILIZATION				LS	
	507	00100	630	FT	STEEL PILES HP10X42, FURNISHED	300	330			
	507	92200	570	FT	PREBORED HOLES	270	300			
	509	10000	26,517	LB	EPOXY COATED STEEL REINFORCEMENT	4,380	4,389	17,748		
	511	34444	87	CY	CLASS QC2 CONCRETE, BRIDGE DECK			87		
	511	43510	68	CY	CLASS QC1 CONCRETE, ABUTMENT INCLUDING FOOTING	34	34			
	512	10100	91	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	15	16	60		
	513	10221	82,900	LB	STRUCTURAL STEEL MEMBERS, LEVEL 1, AS PER PLAN			82,900	2 / 15	
	513	20000	1,260	EACH	WELDED STUD SHEAR CONNECTORS			1,260		
	516	13200	52	SF	1/2" PREFORMED EXPANSION JOINT FILLER			52		
	516	13600	54	SF	1" PREFORMED EXPANSION JOINT FILLER			52	2	
	516	13900	42	SF	2" PREFORMED EXPANSION JOINT FILLER			42		
	516	14014	85	FT	INTEGRAL ABUTMENT EXPANSION JOINT SEAL			85		
	516	44001	10	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), AS PER PLAN (LOAD PLATE 11.5"x14"x1.50", NEOPRENE 10.5"x13"x1.69")			10	8 / 15	
	517	70000	150	FT	RAILING (TWIN STEEL TUBE)			150		
	518	21200	58	CY	POROUS BACKFILL WITH GEOTEKSTILE FABRIC	29	29			
	SPECIAL	51822300	167	FT	STEEL DRIP STRIP			167		
	518	40000	96	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	48	48			
	518	40010	54	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	28	26			
	526	15000	124	SY	REINFORCED CONCRETE APPROACH SLABS (T=13")				124	
	526	90010	56	FT	TYPE A INSTALLATION				56	
	601	32204	193	CY	ROCK CHANNEL PROTECTION, TYPE C WITH GEOTEKSTILE FABRIC	91	102			
	625	33000	1	EACH	STRUCTURE GROUNDING SYSTEM				1 2 / 15	

REMOVE PAY ITEM FOR PILE DRIVING MOBILIZATION

ESTIMATED QUANTITIES
 BRIDGE NO. FAI-C0055-0332
 OVER MUDDY PRAIRIE RUN

SPN	2337259
DESIGN AGENCY	
DLZ	
DESIGNER	CHECKER
JAM	MDP
REVIEWER	
MJL 10/25/24	
PROJECT ID	113793
SUBSET	TOTAL
4	15
SHEET	TOTAL
P.38	49