



## Fairfield County Engineer

3026 W. Fair Ave.  
Lancaster, OH 43130  
Main: (740) 652-2300  
Fax: (740) 687-7055

### **LAKESIDE PHASE 1 DRAINAGE PROJECT**

The following bid questions were asked and answered during the mandatory Prebid Meeting held on March 18, 2026:

1. What is the length of Sanitary Sewer that will need CCTV inspection?


*The length measures 655 feet total.*

2. Will the Township allow concrete in place of the 301 Asphalt Base?

*Yes, the Township will allow concrete, meeting the requirements of ODOT Item 499 QC Misc., to be substituted for the Item 301 Asphalt Concrete Base at the same thickness as shown in the plans. Additionally, this will be paid at the same cubic yard unit cost bid for Item 301.*

3. If the Alternate is accepted, will the Township allow concrete all the way up and then milled off with the mill/fill overlay?

*Should the Alternate Mill and Fill be added to the contract, the Township is acceptable to allow concrete, meeting the requirement of ODOT Item 499 QC Misc., to be substituted for the following Items; Item 301 Asphalt Concrete Base, Item 441 Asphalt Concrete Intermediate Course, Type 2, and Asphalt Concrete Surface Course Type 1 at the same total thickness to bring the repair flush to the grade of the existing roadway. Then the concrete, along with the roadway will be milled and overlaid with asphalt concrete.*

  
Eric T. McCrady, P.E.  
Deputy Engineer

Jeremiah D. Upp, P.E., P.S., County Engineer